

SLUM REHABILITATION AUTHORITY

No: SRA/Maint. Sec./Desk-1/ 44 /2023

Date: 02 - 02 - 2024

E-QUOTATION NOTICE FOR E-TENDER

1. Quotations in sealed covers are invited from the Contractors so as to reach the office of the undersigned at Slum Rehabilitation Authority, Administrative Bldg., Anant Kanekar Marg, Bandra (E), Mumbai- 400 051. on or before 08 / 02 /2024 upto 3.00 p.m. for the work of Providing fully glazed partition on 2nd floor engineering department and Removing old damaged false ceiling and providing new waterproof PVC False ceiling at A wing washrooms and other Miscellaneous works at Slum Rehabilitation Authority, Administrative building, Bandra (East), Mumbai-400051.
2. The estimated cost of the work is Rs.9,55,473/- (Rupees nine lakhs fifty five thousand four hundred and seventy three Only).
3. The quotations in sealed cover shall be addressed to the Executive Engineer Maint/SRA, Slum Rehabilitation Authority, Administrative Bldg., Anant Kanekar Marg, Bandra (E), Mumbai- 400 051. The blank quotations can be downloaded from the tender section of SRA website www.sra.gov.in from 02/02/2023 to 08/02/2024 upto 3.00 p.m.
4. The quotationer shall quote in ink his percentage offer above/below or at par the estimated cost both in figures and words. The quotation should be submitted in a single sealed Envelope containing forwarding letter, quotation notice and duly filled Schedule-B and signed on each page.
5. The name of work for which quotations have been given should be stated clearly on the envelope containing the quotation and name of Contractor should be written on lower left of envelope.
6. The sealed quotation will be received by the office of Executive Engineer Maint./SRA, Slum Rehabilitation Authority, Administrative Bldg., Anant Kanekar Marg, Bandra (E), Mumbai- 400 051. upto 3.00 p.m. by 08/02/2024 and will be opened at 3.30 p.m. on the same day as far as possible in the presence of the contractors/their representatives whosoever remain present at that time.
7. The quantities as shown in Schedule 'B' are approximate. The payment will be made as per actual quantity of work done.
8. The acceptance of quotation shall rest with the competent authority who reserves the right to reject any or all the quotations without assigning any reason for doing so.
9. The quotation submitted by the quotationer shall be binding on him for a period of 60 days from the last date of receipt of quotation.
10. No alternation in the form of quotation or schedule of quantities, specifications shall be entertained.
11. The entire work is to be completed within 30 days.
12. The work shall be carried out in accordance with I.S. specifications for the particular items and as per the detailed specifications mentioned in Schedule-B.
13. The rates quoted shall be inclusive of all taxes, Octroi Duty and free delivery at site of work and nothing extra shall be paid on any account.

14. The quotationer is advised to visit and examine the site of work and its surroundings before quoting the rate and acquaint themselves with the site conditions.
15. The contractor will have to make his/ their own arrangement at his/their cost for office and stores and safeguard the materials brought on the work and the materials issued by the department if any.
16. The contractor shall provide all labours, tools, pegs, watering and all other materials as required for line out and setting out the layout etc. for the work without claiming any payment.
17. After the completion of the work, the contractor shall remove forthwith all his/ their serviceable and un-serviceable materials from site of work and other debris shall be dumped and levelled as ordered within the scope of work if so ordered without any extra cost.
18. No escalation shall be paid to the contractor.

Sd/-

Executive Engineer

Slum Rehabilitation Authority

Issued to:

M/s. _____

Copy to F.C/SRA for information.

Copy to A.E/ SRA, for information and necessary action.

Copy to notice board/SRA.

Copy to information technology department/SRA. For publishing quotation notice along with Abstract on SRA website



SLUM REHABILITATION AUTHORITY

No: SRA/MAINT.SEC./DESK-1/44 /2023

Date: 02-02-2024

Abstract

Subject: Providing fully glazed partition on 2nd floor engineering department and
Removing old damaged false ceiling and providing new waterproof PVC False
ceiling at A wing washrooms and other Miscellaneous works at Slum
Rehabilitation Authority, Administrative building, Bandra (East), Mumbai-
400051.

Sr. No.	Description of item	Quantity	Unit	Rates (rs)	Amount (rs)
<u>Item No.01</u>	Providing & fixing FULL HEIGHT BOTH SIDE LAMINATED PARTITION at required location having height more than 2.8 meter & minimum 77 mm thick made by using 50 x 50 mm (finished size) approved quality seasoned TW section framing at 600 mm center to center, covered with 12 mm marine ply generally confirming to I.S.303 / I.S.710-1980 on both sides. The partitions shall be finished with 1.5 mm thk. approved quality laminate matt/suede/fine line finished lamination pattern with grooves on both sides with necessary lipping (BTC) moulding. Antitermite treatment to plywood and woodwork, door frame including all leads & lifts etc complete as per Architect's Drawing and instructions of Engineer In Charge.	7.00	sq.mt	7270	50890.00
<u>Item No.02</u>	Low Height Storage - providing and fixing on site 40 cm Deep Low Height Storage Unit at required location less than 1.35 meter height by using 19mm marine ply of requisite etc complete work as directed by engineer incharge.	3.40	sq.mt	12695.00	43163.00
<u>Item No.03</u>	Providing and fixing 34 mm thick moulded door shutter consisting of solid core single leaf flush door of 30 mm thickness lipped with 15 mm (5mm x 3) thick x 30 mm width on one style and top rail and 10 mm (5mm x 2) thick x 30 mm width on other style and bottom rails. The inner panels laminated with 2 mm thick termite proof, water proof and fire resistant moulded PVC sheet with 2,4,6 design in different plain and /or prelim colours on one side after routing the moulded design on flush doors and	2.10	sq.mt	7789.95	16358.90

	2 mm plain and /or pre lam PVC on other side using rubber adhesive on flush door and solvent cement adhesive on the PVC lipping etc. as per direction of Engineer in charge and manufacturers specification and drawing etc. complete				
<u>Item No.04</u>	Providing and fixing 1st quality Burma T.W. door frame of size 75 x 150mm with required groove and chamfer including M.S.hold-fast of size and make. Door Type D5-ED as per architect's detailed drg. And design and as instructed by the Engineer-in-charge	5.70	rmt	4096.00	23347.20
<u>Item No.05</u>	Door Closure: (For 2 Hr fire Rated EN-3 Door Closure) Supplying, fitting & fixing Surface mounted overhead Door Closer for 2 hour fire rated doors of different size (e.g size -EN-3 for leaf width upto 900mm) CE certified, marked & conforming to EN - 1154 of approved quality (Internationally reputed brand like Dorma, Geze, Hafele, Assabloy & Magnum etc.) fitted and fixed Complete as per direction & satisfaction of Engineer -in Charge including all taxes & incidental charges	1.00	nos.	4103.40	4103.40
<u>Item No.06</u>	Supplying table cloth (sarj) (Material supplied should be standard company)	9.60	sq.mt	200.00	1920.00
<u>Item No.07</u>	Plain Glass 6mm	2.30	sq.mt	1260.00	2898.00
<u>Item No.08</u>	Providing & fixing FULL HEIGHT FULLY GLAZED PARTITION at required location having height approx.2.80 meter by using 10 mm thick toughened float glass fixed in 50 mm x 100 mm approved quality seasoned T.W. section at top & bottom rail with necessary lipping (BTC) moulding & fixtures etc.complete. Antitermite treatment to woodwork,door frame &melamine polish to all woodwork including all leads & lifts etc complete as per architects Drawing and instructions of Engineer In Charge.	8.20	sq.mt	5531.00	45354.20
<u>Item No.09</u>	Providing and fabricating structural steel work in rolled sections like joists, channels, angles, tees etc. as per detailed design and drawings or as directed including cutting, fabricating, hoisting, erecting, fixing in position making riveted / bolted /welded connections without connecting plates, braces etc. and including one coat of anticorrosive paint and over it two coats of oil painting of approved quality and shade etc. complete	0.10	M.T.	106936.20	10693.62

<u>Item No.10</u>	Providing & fixing premium quality Roller blinds with prestress Solar protection fabric of high tenacity Polyester Yarn with PVC coating and fungi static treatment and should block the light flux & offer elimination of glare and sunlight /radiance etc. complete. Fabric shall have visible light & solar properties & Greengard (gold) Indoor Air quality & children & school certified.	22.40	sq.mt	2118.00	47443.20
<u>Item No.11</u>	Mazdoor - Unskilled Heavy Male	35.00	Day	645.75	22601.25
<u>Item No.12</u>	Providing and applying plaster / wall punning with plaster of paris (with plaster of paris material) in 10 to 13 millimeter thickness to previously plastered surface / or on newly brick surface (Excluding rough cast plaster) in all position including preparing and Finishing the surface scaffolding etc.complete	16.60	sq.mt	600.60	9969.96
<u>Item No.13</u>	Dismantling aluminium/ Gypsum partitions, doors, windows, fixed glazing and false ceiling including disposal of unserviceable surplus material and stacking of serviceable material with in 50 meters lead as directed by Engineer-in-charge	60.60	sq.mt	42.00	2545.20
<u>Item No.14</u>	Providing and Fixing Channelled perforated panels of width 192mm, thickness of 15mm and length 2400 mm, made of a Moisture resistant fibre board substrate with a laminated facing as per the approved shade (Portland Maple, Sea Beech, Siam Wood & Mystique Walnut, Interior White, Alumina Pearl) and a melamine balancing layer on the reverse side. The boards shall have a special perforation pattern where the reverse surface has a "Helmholtz" fluted perforation with consecutive 3mm wide groove followed by 13mm or 21mm of visible pane (G-13/ G-21). The edges of the panel shall be "tongue-and-grooved" to fix special clips for installation and seamless visual. The back of the perforated panel shall have sound absorbing non-woven Soundtex acoustical fleece hot pressed to achieve NRC of 0.5. for G-21 and 0.6 for G-13. (Average value of Absorption Co-efficient readings taken at 250 Hz, 500 Hz, 1000 Hz and 2000 Hz) as per ASTM C423 and Humidity Resistance (RH) of 70% with camber limit less than 1mm/1000mm and bow less than 1mm/300mm One Metric Tonne panels shall be mounted on special aluminium splines (keel) using inside clips provided by Manufacturer and approved by the Architect/ Engineer-in-Charge.	60.60	sq.mt	5251.00	318210.60

<p><u>Item</u> <u>No.15</u></p>	<p>Providing and fixing in position Gypsum board false ceiling with 12.5 mm thick Gypsum boards, screwed/fixed to the under structure of suspended G.I. Grid constructed and suspended from the main ceiling consisting of ceiling sections of size 25 x 50 mm maximum center to center distance of 600 milimetre perimeter channel and intermediate channels at maximum center to center distance 1200 milimetre galvanized grid should be fixed to reinforced cement concrete slab. The gypsum board should be fixed to galvanized iron grid with necessary screws. The boards should be taped and filled from underside to give smooth, seamless ceiling. The rate should include necessary additional ceiling sections and intermediate channels. Additional intermediate channels should be fixed to strap hangers for additional support to prevent strapping at every 1200 milimetre item to be completed in all respect including necessary sleeves for ducts finishing of joints cut outs, painting including labour, material, lifts etc. all complete</p>	45.30	sq.mt	1857.45	84142.49
<p><u>Item</u> <u>No.16</u></p>	<p>Providing and applying Royale Luxury Emulsion of approved make on internal wall surface as detailed below Scrapping for surface with emery paper and wipe clean for area. wall primer with brush by adding mineral turpentine oil by 8 to 10 % or water by 15 to 20% allowing to dry for 6 to 8 hoursAfter applying acrylic wall putty with appropriate prpportion of water of allow to dry for period of 4 to 6 hours of activity. Scrapping with emery paper and wipe clean Applying paints Royale Luxury emulsion 1st coat with brush water content water 40 to 45% or 65 to 70% by role Applying paints Royale luxury emulsion 2nd coat with brush with water content 40 to 45% or 65 to 70 % by roller. (With prior approval of S.E.)</p>	34.40	sq.mt	288.75	9933.00
<p><u>Item</u> <u>No.17</u></p>	<p>Providing and fixing Oval Type Under Counter Wash Hand Basin of 420 x 590 x 195mm size with pillar cock, C.P.Angular stop cock, long thread of approved make continental including SS bottle trap of necessary pipe connection up to the outside face of the wall, having Telephonic Black / Colour Granite of 180 mm thick fixed on Black Kadappa Framework, etc. Complete as directed by Engineer in charge.</p>	1	per no.	20883.45	20883.45

<u>Item No.18</u>	Providing and fixing Table top white wash basin of size 120x635x405mm rubber plugs and brass chain, with pillar cock, C.P.Angular stop cock long thread, continental including S.S. bottle trap of approved make having necessary pipe connection up to the outside face of the wall.etc complete as directed by Engineer in charge.	2	per no.	25573.80	51147.60
<u>Item No.19</u>	Providing and fixing white european type wall-hung pan, of size 350mm x 355mm x 570 mm concealed flush tank with floor-mounting frame installing kit and drain pipe connection set for wall hung WC, with approved make square control plates including soil pipe, vent pipe upto the outside face of wall, 100mm dia C.I. plug bend inlet pipe all fittings, cutting & making good walls, floors etc. complete.	1	per no.	31969.35	31969.35
<u>Item No.20</u>	Providing and laying in trenches 32 mm dai. CPVC pipe including necessary excavation, fittings. Refilling trenches etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	20	rmt	502.95	10059.00
<u>Item No.21</u>	Bib cock stop tap brass heavy 25mm	2	NO.	1044.75	2089.50
Total Estimated Cost					809722.91
CGST 9%					72875.06
SGST 9%					72875.06
Total					955473.03
Say Rupees 9,55,473/-					

I/We hereby agree to quote _____% Above/Below or At Par with the estimated cost put to the tender. Therefore, the amount _____ (in words)

_____.

Sd/-

Executive Engineer
Slum Rehabilitation Authority